

Apr 28 2006 (Update Data)

WATER AND AIR HEAT LOAD

Data As of APR 28 2006

MAIN LINAC - ELECTRON & POSITRON											
Components	Quantity	Location	Total Heat Load (KW)	To Deionized Water					To Air		Source
				Heat Load to Water (KW)	Supply Temp (variation) (C)	Delta Temperature (C delta)	Maximum Allowable Pressure (Bar)	Typical (water) pressure drop Bar	Acceptable Temp Variation delta C	Heat Load to Air (KW)	
RF AC Pwr Transformer 34.5-.48 kV		Service Tunnel	4.00	0.00						4	* Clay email 3-14-06 typical 225 kVa oil xfmr
AC Pwr Transformer 34.5-.48 kV		Service Tunnel	2.00	0.00						2	* Clay email 3-14-06 typical 112.5 kVa oil xfmr
Emerg. AC Pwr Transformer 34.5-.48 kV		Service Tunnel	1.00	0.00						1.3	* Clay email 3-14-06 typical 75 kVa oil xfmr
DC Charging Supply 0.48KvAC-11KvDC		Service Tunnel	7.50	6.00						1.5	* C.Jensen email 2-27-06 183 kVa 0.84pf oil ps xfmr **Shigeki Apr 18 2006
Modulator		Service Tunnel	7.50	3.50						4	* Shigeki Fukuda Email 3-1-06 **Shigeki Apr 18 2006
Pulse Transformer		Service Tunnel	6.00	5.00						1	**Shigeki Apr 18 2006
Klystron Socket Tank		Service Tunnel	1.00	1.00						0	**Shigeki Apr 18 2006
Klystron Focusing Coil		Service Tunnel	8.40	8.40	*34>					0	* Shigeki Fukuda Email 4-05-06
Klystron Collector		Service Tunnel	61.00	61.00	*35>			2		0	* Shigeki Fukuda Email 3-1-06
Klystron Body		Service Tunnel	10.00	10.00	*35>			5	None	0	* Shigeki Fukuda Email 3-1-06
Klystron Windows		Service Tunnel	0.50	0.50	*35>			1		0	* Shigeki Fukuda Email 3-1-06
Relay Racks		Service Tunnel	13.3	11.3	N/A	N/A		N/A		0	* Shigeki Fukuda Email 3-30-06 **Shigeki Apr 18 2006 (chilled water)
Circulators & Dummy Load		Accelerator Tunnel	24.3	24.3						0.00	**Shigeki Email Apr 28 2006
Waveguide		Accelerator Tunnel	4.00	4.00	N/A	N/A		N/A		0.00	* Shigeki Fukuda Email 3-30-06
Other components?????		????								N/A	
Total			150.5	135.0						13.8	


RF Component only Loads 143.45

Total Heat load to Air & Chilled water per RF	25.1 kW
Total Heat load to LCW per RF	124 kW

Total Heat Load (Accelerator Tunnel)	28.30	28.3 KW	0.00
Total Heat Load (Service Tunnel)	122.15	106.7 KW	13.80

~124KW per RF for LCW


~25 KW per RF for Chilled Water



Electron Main Linac has a total of 312 RF unit-that equate to 312 LCW Skid per each Linac (Main Linac only) @ ~124 KW heat load each skid. (assume each skid per RF).

TEMPERATURE UPDATE: Supply Temp 95F (35C)ok. Assume 18F to 20 F (10 – 11 C)delta

WATER PLANT SIZE



water cooling - main linac RF

Apr 5 2006

Can cost this now

Up to Header only